


**HENRY PRODEQ WATER CONTAINMENT SYSTEM  
SEQUENCE OF INSTALLATION**

- ① DECK/SUBSTRATE AS SPECIFIED
- ② PRIMER (SEE NOTE #2)
- ③ WATERPROOFING MEMBRANE:  
**HENRY PRODEQ FX 600**  
OR **HENRY PRODEQ FX 650** (100 MILS)



**NOTES:**

- 1. DETAIL SHOWS HENRY **PRODEQ** WATER CONTAINMENT SYSTEM. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
- 2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** WATER CONTAINMENT SYSTEM IS **HENRY GC EPOXY PRIMER**. OTHER RECOMMENDED PRIMER(S) INCLUDE: **HENRY ST PRIMER** WITH AGGREGATE. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
- 3. DO NOT INSTALL **PRODEQ** WATER CONTAINMENT SYSTEM BEYOND PRIMED SURFACES.
- 4. REFER TO **PRODEQ** WATER CONTAINMENT SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.



A **CARLISLE** COMPANY

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATER CONTAINMENT SYSTEM**

**SYSTEM DETAIL**

**TYPICAL PRODEQ WATER CONTAINMENT SYSTEM  
PRODEQ FX 600 OR PRODEQ FX 650**

SCALE: N.T.S. | 06-17-2022

**PDEQ-CS-A1**