



Notes:

1. Detail shows 2 ply reinforced 790-11EV membrane installed over concrete deck.
2. Refer to Henry 790-11EV Guide Specifications and Technical Data Sheets for installation procedures.
3. Vegetation to be no closer than 12 inches to drain.



790-11EV WATERPROOFING MEMBRANE

SCALE: N.T.S.

TYPICAL VRA ROOF ASSEMBLY

10-20-10

ROOF DRAIN
 DETAIL

VR-10